

ADDENDUM NO. 1

April 3, 2023

SW Nottingham Rd. – SW 33rd to SW 37th St.
Full-Depth Pavement Reclamation Project
S-841012.00

TO ALL PROSPECTIVE BIDDERS:

This addendum is included with the Contract Documents for the SW Nottingham Rd. – SW 33rd to SW 37th St. Full-Depth Pavement Reclamation Project, S-841012.00. Acknowledge receipt of this addendum in the space provided under Article 3 of the Bid Form and include a copy of this page with the bid submittal.

The following clarifications are added to the project:

- 1) Shawnee County will require a cement slurry mixture to be utilized for Subgrade Treatment (Cement)(8").
 - a. **Cement Slurry Equipment.** Contractor shall use slurry tanks equipped with agitation devices to slurry cement on the project or other approved location. Equip the distributor truck with an approved sampling device.
 - b. **Slurry Placement.** Contractor shall mix the required quantity of cement with water, as approved. Provide slurry free of objectionable materials and with a uniform consistency that can be easily applied. Agitate the slurry continuously. Apply slurry within 2 hours of adding water and when the roadway is at a moisture content drier than optimum. Distribute slurry uniformly by making successive passes over a measured section of the roadway until the specified cement content is reached.
- 2) The bid item, Pavement Removal (SY), shall include removal of existing materials 8" below proposed road elevations shown on plans, regardless of thickness of existing pavement. This work will be Subsidiary to Pavement Removal (SY).



Brian T. Austin, PE
Project Manager
SBB Engineering LLC

ACKNOWLEDGEMENT:

The undersigned hereby acknowledges receipt of Addendum No. 1 for S-841012.00.

Contractor

Date: _____

By: _____

Please acknowledge this addendum by signing above and returning with the bid form. It is required that this Addendum No. 1 also be acknowledged with the Document 330-Bid Form submittal.